



# WILLIAM THOMSON

## WILLIAM THOMSON



ULE⊽

### DP 2 Cable-laying vessel

#### **TECHNICAL SPECIFICATIONS**

Maximum cable load	28,000 t
Turntable capacity	2 x 11,000 t + 1 x 7,500 t
Length o.a.	215 m
Breadth	40 m
Draught loaded	9.75 m
Draught empty	5.5 m
Propulsion power	4 x 2,600 kW Azimuth thrusters
Bow thruster power	3 x 2,100 kW
Retractable thruster power	2 x 2,600 kW
Total installed diesel power	30,600 kW
Speed max.	13.5 kn
Accommodation	120 persons
Built in	under construction - 2026

#### SPECIFICATION OF OPERATIONAL EQUIPMENT

Deck carousel	2 x 11,000 t Inner diameter 8 m
Under deck carousel	7,500 t Inner diameter 8 m
Fibre optic tanks	2 x 600 t
Tensioners	Laying: 3 x 50 t – 4 tracks Loading: 2 x 7.5 t – 2 tracks
Laying wheel	integrated in stern chute 12 m diameter
Offshore cranes	100 t AHC 30 t
ROVs	2 x WROV in dedicated ROV hall 3,000 m depth rating
Winch	150 t AHC abandonment & recovery winch
Poinforced construction for ploughing A-frame	

Reinforced construction for ploughing A-frame

The vessel can install up to 28,000 t of cable and is thereto equipped with two 11,000 t turntables above deck, a 7,500 t turntable below deck and two fibre optic tanks, along with three 50 t tensioners, a cable laying chute and a cable laying wheel. The vessel is capable of laying up to five cables simultaneously.

#### NEXT GENERATION TECHNOLOGY

Hybrid power plant with 2.5 MWh battery system ULEv technology

Green fuel solutions: operation on biofuel and methanol





The content of this document is provided strictly for information purposes only. Whilst it has been endeavoured to procure completeness and accuracy, no warranty - express or implied - is given, in particular of fitness for a particular purpose. In no event any Jan De Nul Group company will be liable for any whatsoever damages arising directly or indirectly from the use of or reliance on the content provided herein, even if (previous) advice has been given/received that such damages may occur.

